GENERAL INFORMATION

OWNER

MAP 494Z LOT 44 UNITIL ENERGY SYSTEMS INC. NATHAN SHERWOOD, P.E. 6 LIBERTY LANE WEST HAMPTON, NH 03824

APPLICANT

603-773-6476

UNITIL ENERGY SYSTEMS INC. NATHAN SHERWOOD, P.E. 30 ENERGY WAY EXETER, NH 03833 603-773-6476

RESOURCE LIST

PLANNING, ZONING & COMMUNITY DEVELOPMENT DEPARTMENT 41 GREEN STREET, 3RD FLOOR CONCORD, NH 03301 603-225-8595 603-225-8515

ANNE-MARIE SKINNER, CITY PLANNER CODE ADMINISTRATION

MATTHEW WALSH, DEPUTY CITY

MANAGER-DEVELOPMENT &

37 GREEN STREET CONCORD, NH 03301 603-225-8580 DAVID HALL, CODE ADMINISTRATOR

CITY MANAGER 41 GREEN STREET CONCORD, NH 03301 603-225-8570 THOMAS J. ASPELL JR., CITY MANAGER

GENERAL SERVICES (PUBLIC WORKS) 311 NORTH STREET CONCORD, NH 03301

603-230-3929 KEVIN DEMERS, ASSISTANT SUPERINTENDENT POLICE DEPARTMENT 35 GREEN STREET

BRADLEY C. OSGOOD, CHIEF OF POLICE FIRE DEPARTMENT 24 HORSESHOE POND LANE CONCORD, NH 03301 603-230-3804

ASSOCIATED PROFESSIONALS

PAUL SIROIS, FIRE MARSHALL

CONCORD, NH 03301

603-225-8600

LIGHTING DESIGN EXPOSURE LIGHTING 501 ISLINGTON ST, UNTI 1A

PORTSMOUTH, NH 03801 603-601-8080

KEN SWEENEY, APPLICATIONS ENGINEER

ABUTTERS

TAX MAP 582Z LOT 1 SMOKESTACK REALTY, LLC 345 BAPTIST ROAD CANTERBURY, NH 03224

TAX MAP 58Z LOT 18 CHERYL GOCHEZ 2006 REV. TRUST 345 BAPTIST ROAD CANTERBURY, NH 03224

TAX MAP 58Z LOT 17 CLAUDIA HANNON REV. TRUST C/O ALEXIS B GATTO TRUSTEE 507 SOUTH BLVD. APT B SALISBURY, MD 21801-5875

TAX MAP 58Z LOT 16 MT NEST, LLC 98 ROBINSON ROAD

HUDSON, NH 03051

TAX MAP 58Z LOT 15 PETER J & CASSANDRA DENONCOURT 268 N STATE STREET CONCORD, NH 03301

TAX MAP 58Z LOT 14 JULIA & GALEN MARSH JR 272 N STATE STREET CONCORD, NH 03301

TAX MAP 58Z LOT 13 AYODEJO AKINOLA 274 N STATE STREET

CONCORD, NH 03301-3224 TAX MAP 58Z LOT 12 DARTNELL PROPERTIES, LLC 121 SARAH CIRCLE

LACONIA, NH 03246-3069

TAX MAP 494Z LOT 32 BOSTON & MAINE CORP. C/O PAN AM RAILWAYS, INC. 1700 IRON HORSE PARK NORTH BILLERICA, MA 01862-1641

TAX MAP 494Z LOT 43 STATE OF NH C/O DEPARTMENT OF CORRECTIONS PO BOX 1806 CONCORD, NH 03302-1806

TAX MAP 494Z LOT 42 STATE OF NH C/O SECRETARY OF STATE 107 N MAIN STREET

CONCORD, NH 03301-4951

NORTH BILLERICA, MA 01862

TAX MAP 743Z LOT 10-2 NORTHERN RAILROAD C/O PAN AM RAILWAYS, INC. 1700 IRON HORSE PARK

TAX MAP 49Z LOT 3 CITY OF CONCORD C/O ABUTTS R&R ROW 41 GREEN STREET CONCORD, NH 03301-4255

TAX MAP 949Z LOT 40 BENJAMIN T CARBONE -2 CHURCHILL DRIV HOOKSETT, NH 03106-4702

WEST CONCORD SUBSTATION

1-7 MCGUIRE STREET CONCORD, NEW HAMPSHIRE



NICHOLAS GOLON No. 14086

REVISED PER CITY COMMENTS 1 9/22/25 REV DATE DR CK **DESCRIPTION**

INDEX OF SHEETS SHEET TITLE SHEET COVER SHEET C - 02NOTES & LEGEND C - 03NOTES SHEET 1 OF 1 EXISTING CONDITIONS SURVEY PLAN C - 04SITE PREPARATION & DEMOLITION PLAN C - 05OVERALL SITE LAYOUT PLAN C-06 SITE LAYOUT PLAN C - 07GRADING, DRAINAGE & UTILITY PLAN C-08 STORMWATER MANAGEMENT PLAN C-09 LANDSCAPING PLAN

TURNING MOVEMENT PLAN

DETAILS

LIGHTING PLAN

REFERENCE PLANS BY ASSOCIATED PROFESSIONALS

T - 01

D-01 TO D-04

PERMITS/APPROVALS							
	NUMBER	APPROVED	EXPIRES				
CITY OF CONCORD SITE PLAN APPROVAL	_	_	_				
CITY OF CONCORD CUP ARTICLE 28.2.4 (USE)	_	_	_				
CITY OF CONCORD CUP ARTICLE 28.4.4 (SHORELAND BUFFER)	_	_	_				
NHDES AOT PERMIT	_	_	_				
CITY OF CONCORD DRIVEWAY PERMIT	_	_	_				
NHDES SHORELAND PERMIT	_	_	_				
EPA NPDES ENOI CGP & SWPPP	_	_	_				

WAIVERS

THE FOLLOWING WAIVERS FROM THE CITY OF CONCORD SITE PLAN REVIEW REGULATIONS ARE <u>REQUESTED</u> FROM THE PLANNING BOARD: 1. CITY OF CONCORD STANDARD DETAILS SECTION 3(2)(C) 2. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.03(7) 3. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.03(8) 4. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.03(16) 5. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.03(17) 6. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.03(18) 7. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.03(23) 8. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 15.04(6) 9. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 20.06 10. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 26.02 11. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 26.03 12. CITY OF CONCORD SITE PLAN REGULATIONS SECTION 6.03(2)(c) & 11.05



SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

COVER SHEET

UNITIL WEST CONCORD SUBSTATION 1-7 MCGUIRE STREET, CONCORD, NH 03301

UNITIL ENERGY SYSTEMS, INC. 6 LIBERTY LANE WEST, HAMPTON, NH 03824 UNITIL ENERGY SYSTEMS, INC.

30 ENERGY WAY, EXETER, NH 03833

SCALE: AS NOTED

AUGUST 20, 2025



Civil Engineers Structural Engineers Traffic Engineers and Surveyors Landscape Architects 48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com

96159-01 DR PL FB CK NG CADFILE 96159-01 COVER & DETAILS C - 01

without the prior written permission of TFMoran, Inc. This plan is not effective unless signed by a duly authorized officer of TFMoran, Inc.

All rights reserved. These plans and materials may not be copied,

duplicated, replicated or otherwise reproduced in any form whatsoever

Copyright 2025 ©TFMoran, Inc.

48 Constitution Drive, Bedford, N.H. 03110


APPROVED

UNDER THE PROVISIONS OF R.S.A. 674:35 & R.S.A. 674:36

CITY PLANNING BOARD CITY OF CONCORD, NEW HAMPSHIRE

in accordance with vote of the board dated:

Approval of this plan is limited to the lots as shown



ABBREVIATIONS								
			GENERAL			UTILITIES		
ABAN	ABANDON	EP	EDGE OF PAVEMENT	OC	ON CENTER	CB	CATCH BASIN	
AC	ACRES	EXIST	EXISTING	PAVE	PAVEMENT	CIP	CAST IRON PIPE	
ADJ	ADJUST	FFE	FINISHED FLOOR ELEVATION	PERF	PERFORATED	CMP	CORRUGATED METAL PIPE	
APPROX	APPROXIMATE	FND	FOUNDATION	PROP	PROPOSED	СО	CLEANOUT	
ВС	BOTTOM OF CURB	HP	HIGH POINT	R	RADIUS	COND	CONDUIT	
BIT	BITUMINOUS	INV	INVERT ELEVATION	R&D	REMOVE AND DISPOSE	DCB	DOUBLE CATCH BASIN	
BK/PG	BOOK & PAGE	ΙΤ	INFILTRATION TEST	R&R	REMOVE AND RESET	DIP	DUCTILE IRON PIPE	
BLDG	BUILDING	L	LENGTH	REM	REMOVE	DMH	DRAIN MANHOLE	
BMP	BEST MANAGEMENT PRACTICE	LF	LINEAR FEET	RET	RETAIN	F&C	FRAME AND COVER	
BS	BOTTOM OF SLOPE	LSA	LANDSCAPE AREA	RIM	RIM ELEVATION	F&G	FRAME AND GRATE	
BW	BOTTOM OF WALL	MAX	MAXIMUM	ROW	RIGHT OF WAY	FES	FLARED END SECTION	
CONC	CONCRETE	MIN	MINIMUM	S	SLOPE	GT	GREASE TRAP	
COORD	COORDINATE	N/F	NOW OR FORMERLY	SF	SQUARE FEET	HDPE	HIGH DENSITY POLYETHYLENE PIPE	
DIA	DIAMETER	NHFG	NEW HAMPSHIRE FISH & GAME	SW	SIDEWALK	HH	HANDHOLE	
ELEV	ELEVATION	NTS	NOT TO SCALE	TBM	TEMPORARY BENCHMARK	HW	HEADWALL	
Conveight 202	5 ©TFMoran, Inc.			TC	TOP OF CURB	HYD	HYDRANT	
	n Drive, Bedford, N.H. 03110			TP	TEST PIT	LP	LIGHT POLE	
40 Constitutio	ii blive, bealord, N.II. 03110			TW	TOP OF WALL	ocs	OUTLET CONTROL STRUCTURE	
All rights reserved. These plans and materials may not be copied,				TYP	TYPICAL	PVC	POLYVINYL CHLORIDE PIPE	
duplicated, replicated or otherwise reproduced in any form whatsoever			UG	UNDERGROUND	RCP	REINFORCED CONCRETE PIPE		
without the prior written permission of TFMoran, Inc.			WCR	ACCESSIBLE WHEELCHAIR RAMP	RD	ROOF DRAIN		
			W/	WITH	SMH	SEWER MANHOLE		
This plan is not effective unless signed by a duly authorized officer of			icer of			SOS	SEDIMENT OIL SEPARATOR	
TFMoran, Inc.						TSV	TAPPING SLEEVE, VALVE, AND BOX	
						UP	UTILITY POLE	

GENERAL NOTES

ELEVATIONS PRIOR TO CONSTRUCTION.

- THESE PLANS WERE PREPARED UNDER THE SUPERVISION OF A LICENSED PROFESSIONAL ENGINEER. TFMORAN, INC. ASSUMES NO LIABILITY AS A RESULT OF ANY CHANGES OR NON-CONFORMANCE WITH THESE PLANS EXCEPT UPON THE WRITTEN APPROVAL OF THE ENGINEER OF RECORD.
- 2. THE SITE CONTRACTOR SHALL NOTIFY THE ENGINEER ONE WEEK IN ADVANCE OF CONSTRUCTION OF EACH STORMWATER FACILITY TO COORDINATE REQUIRED INSPECTIONS. THE CONTRACTOR SHALL TAKE PROGRESS PHOTOS DURING CONSTRUCTION OF ALL
- STORMWATER DRAINAGE COMPONENTS AND SEND TO THE ENGINEER. 3. SEE EXISTING CONDITIONS PLAN FOR THE HORIZONTAL AND VERTICAL DATUM. VERIFY TBM
- 4. CONTACT EASEMENT OWNERS PRIOR TO COMMENCING ANY WORK WITHIN EASEMENTS.
- 5. PRIOR TO COMMENCING ANY SITE WORK, ALL LIMITS OF WORK SHALL BE CLEARLY MARKED IN THE FIELD.
- 6. SITE WORK SHALL BE CONSTRUCTED FROM A COMPLETE SET OF PLANS, NOT ALL FEATURES ARE DETAILED ON EVERY PLAN. THE ENGINEER IS TO BE NOTIFIED OF ANY CONFLICT WITHIN THIS PLAN SET
- 7. TFMORAN, INC. ASSUMES NO LIABILITY FOR WORK PERFORMED WITHOUT AN ACCEPTABLE PROGRAM OF TESTING AND INSPECTION AS APPROVED BY THE ENGINEER OF RECORD.
- 8. PRIOR WRITTEN PERMISSION FROM THE LOCAL PERMITTING AUTHORITY IS REQUIRED IF CLOSURE/OBSTRUCTIONS TO ROADS, STREET, WALKWAYS, AND OTHERS IS DEEMED NECESSARY. CONTRACTOR TO PROVIDE ALTERNATE ROUTES AROUND CLOSURES/OBSTRUCTIONS PER LOCAL/STATE/FEDERAL REGULATIONS.
- 9. REFER TO ARCHITECTURAL PLANS FOR LAYOUT OF BUILDING FOUNDATIONS AND CONCRETE ELEMENTS WHICH ABUT THE BUILDING SUCH AS STAIRS. SIDEWALKS, LOADING DOCK RAMPS PADS, AND COMPACTOR PADS. DO NOT USE SITE PLANS FOR LAYOUT OF FOUNDATIONS.
- 10. IN THE EVENT OF A CONFLICT BETWEEN PLANS, SPECIFICATIONS, AND DETAILS, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATION.
- 11. IF CONDITIONS AT THE SITE ARE DIFFERENT THAN SHOWN ON THE PLANS, THE ENGINEER SHALL BE NOTIFIED PRIOR TO PROCEEDING WITH THE AFFECTED WORK.
- 12. CONTRACTOR'S GENERAL RESPONSIBILITIES:
- A. BID AND PERFORM THE WORK IN ACCORDANCE WITH ALL LOCAL, STATE, AND NATIONAL CODES, SPECIFICATIONS, REGULATIONS, AND STANDARDS AND CONDITIONS OF ALL PROJECT-SPECIFIC PERMITS AND APPROVALS AS LISTED ON THE COVER SHEET TO THESE PLANS OR OTHERWISE REQUIRED.
- B. NOTIFY ENGINEER IN WRITING OF ANY DISCREPANCIES IN PROPOSED LAYOUT AND IN EXISTING FEATURES.
- C. EMPLOY A LICENSED SURVEYOR TO DETERMINE ALL LINES AND GRADES AND LAYOUT OF SITE ELEMENTS AND BUILDINGS.
- D. THE CONTRACTOR SHALL BE RESPONSIBLE TO BECOME FAMILIAR WITH THE SITE AND ALL SURROUNDING CONDITIONS. NOTIFY ALL APPROPRIATE AUTHORITY OF CONSTRUCTION ACTIVITIES REQUIRING TESTS OR INSPECTIONS IN ADVANCE.
- E. TAKE APPROPRIATE MEASURES TO MINIMIZE NOISE, DUST, AND DEBRIS. CONSTRUCTION ACTIVITIES SHALL BE CARRIED OUT IN ACCORDANCE WITH THE APPLICABLE MUNICIPAL ORDINANCES AND REGULATIONS OF THE CITY OF CONCORD.
- F. MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY WORK AT ALL TIMES.
- G. IN ACCORDANCE WITH RSA 430:53 AND AGR 3800, THE CONTRACTOR SHALL NOT TRANSPORT INVASIVE SPECIES OFF THE PROPERTY, AND SHALL DISPOSE OF INVASIVE SPECIES ON-SITE IN A LEGAL MANNER.
- H. COORDINATE WITH ALL UTILITY COMPANIES AND CONTACT DIGSAFE (811 OR 888-344-7233) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION.
- I. PROTECT NEW AND EXISTING BURIED UTILITIES DURING ALL SITE WORK. DAMAGED UTILITIES SHALL BE REPAIRED OR REPLACED AT NO ADDITIONAL COST TO THE OWNER.
- J. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MEANS AND METHODS OF CONSTRUCTION AND FOR CONDITIONS AT THE SITE. THESE PLANS, PREPARED BY TFMORAN, INC., DO NOT EXTEND TO OR INCLUDE SYSTEMS PERTAINING TO THE SAFET) OF THE CONSTRUCTION CONTRACTOR OR THEIR EMPLOYEES, AGENTS, OR REPRESENTATIVES IN THE PERFORMANCE OF THE WORK. THE SEAL OF THE SURVEYOR OR ENGINEER HEREON DOES NOT EXTEND TO ANY SUCH SAFETY SYSTEMS THAT MAY NOW OR HEREAFTER BE INCORPORATED INTO THESE PLANS. THE CONSTRUCTIO CONTRACTOR SHALL PREPARE OR OBTAIN THE APPROPRIATE SAFETY SYSTEMS WHICH MAY BE REQUIRED BY THE US OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) AND/OR LOCAL REGULATIONS.
- K. WRITTEN DIMENSIONS HAVE PRECEDENCE OVER SCALED OR COORDINATE DIMENSIONS. IN CASE OF CONFLICT BETWEEN THIS PLAN SET AND ANY OTHER DRAWING AND/OR SPECIFICATION, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY FOR CLARIFICATIONS.
- L. PROVIDE AN AS-BUILT PLAN AT THE COMPLETION OF THE PROJECT AS REQUIRED BY CONCORD REGULATIONS.
- M. IF ANY DEVIATIONS FROM THE APPROVED PLANS AND SPECIFICATIONS HAVE BEEN MADE, THE SITE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS STAMPED BY A LICENSED SURVEYOR OR QUALIFIED ENGINEER ALONG WITH A LETTER STAMPED BY A QUALIFIED ENGINEER DESCRIBING ALL SUCH DEVIATIONS, AND BEAR ALL COSTS FOR PREPARING AND FILING ANY NEW PERMITS OR PERMIT AMENDMENTS THAT MAY BE
- N. THE CONTRACTOR SHALL PROVIDE THE FOLLOWING DOCUMENTATION TO OWNER AND ENGINEER:
 - 1) ADVANCE WRITTEN NOTICE AT LEAST ONE WEEK PRIOR TO COMMENCING ANY WORK UNDER THE PERMIT AND NOTIFICATION TO AOT VIA THE START OF CONSTRUCTION FORM.
- 2) IF ANY UNDERGROUND DETENTION SYSTEMS, INFILTRATION SYSTEMS, OR FILTERING SYSTEMS WERE INSTALLED, FOR EACH SUCH SYSTEM:
 - A) REPRESENTATIVE PHOTOGRAPHS OF THE SYSTEM AFTER COMPLETION BUT PRIOR TO BACKFILLING; AND
 - B) A LETTER SIGNED BY THE ENGINEER WHO OBSERVED THE SYSTEM PRIOR TO BACKFILLING, THAT THE SYSTEM CONFORMS TO THE APPROVED PLANS AND SPECIFICATIONS.
- 3) UPON COMPLETION OF CONSTRUCTION, WRITTEN CERTIFICATION THAT:
 - A) ALL WORK HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS.
 - B) IF ANY DEVIATIONS FROM THE APPROVED PLANS WERE MADE, WRITTEN DESCRIPTIONS AND AS-BUILT DRAWINGS OF ALL SUCH DEVIATIONS, STAMPED BY A QUALIFIED ENGINEER, SHALL BE PROVIDED.

GRADING & DRAINAGE NOTES

- 1. THE CONTRACTOR SHALL ENSURE THAT ALL WORK INCLUDING INSPECTIONS AND TESTS IS PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF NHDES ENV-WQ 1500 AS APPLICABLE.
- 2. THE CONTRACTOR SHALL PREPARE, MAINTAIN, AND EXECUTE A S.W.P.P.P. IN ACCORDANCE WITH EPA REGULATIONS AND THE CONSTRUCTION GENERAL PERMIT.
- 3. THE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO SUBMIT AN eNOI AT LEAST 14 DAYS IN ADVANCE OF ANY EARTHWORK ACTIVITIES AT THE SITE
- 4. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CHECK THE ACCURACY OF THE TOPOGRAPHY AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO ANY EARTHWORK BEING PERFORMED ON THE SITE. NO CLAIM FOR EXTRA WORK WILL BE CONSIDERED FOR PAYMENT AFTER EARTHWORK HAS COMMENCED.
- 5. THE CONTRACTOR SHALL REFER TO THE GEOTECHNICAL REPORT FOR INFORMATION ABOUT SOIL AND GROUNDWATER CONDITIONS. THE CONTRACTOR SHALL FOLLOW THE GEOTECHNICAL ENGINEER'S RECOMMENDED METHODS TO ADDRESS ANY SOIL AND GROUNDWATER ISSUES THAT ARE FOUND ON SITE, INCLUDING AND NOT LIMITED TO DEWATERING METHODS, PERIMETER DRAINS AND TIE INTO STORMWATER MANAGEMENT SYSTEM, ETC.
- 6. COORDINATE WITH GEOTECHNICAL/STRUCTURAL PLANS FOR SITE PREPARATION AND OTHER BUILDING INFORMATION.
- 7. COORDINATE WITH ARCHITECTURAL PLANS FOR DETAILED LAYOUT AND GRADING AT BUILDING, AND SIZE AND LOCATION OF ALL BUILDING SERVICES, FOOTING DRAINS, AND ROOF DRAIN INFORMATION.
- 8. LIMITS OF WORK ARE SHOWN AS APPROXIMATE. THE CONTRACTOR SHALL COORDINATE ALL WORK TO PROVIDE SMOOTH TRANSITIONS. THIS INCLUDES GRADING, PAVEMENT, CURBING, SIDEWALKS, AND ALIGNMENTS.
- 9. THE CONTRACTOR SHALL PROVIDE A FINISH PAVEMENT SURFACE FREE OF LOW SPOTS AND PONDING AREAS. CRITICAL AREAS INCLUDE BUILDING ENTRANCE, RAMPS, AND LOADING
- 10. THE SITE SHALL BE GRADED SO ALL FINISHED PAVEMENT HAS POSITIVE DRAINAGE AND
- 11. ALL ELEVATIONS SHOWN AT CURB ARE TO THE BOTTOM OF CURB UNLESS OTHERWISE
- NOTED. CURBS HAVE A 6" REVEAL UNLESS OTHERWISE NOTED.
- 12. ALL SIDEWALK AND OTHER CURB REVEALS SHALL BE 6" WITH A TOLERANCE OF PLUS OR MINUS 3/8". WHERE SIDEWALK IS TO BE FLUSH, THE PAVEMENT REVEAL SHALL BE WITHIN
- 13. THE FINISHED GRADE AT BOTTOM OF ALL ACCESSIBLE RAMPS SHALL BE FLUSH WITH PAVEMENT WITH A TOLERANCE OF PLUS OR MINUS 1/4".
- 14. ADJUST ALL MANHOLES, CATCH BASINS, CURB BOXES, ETC. WITHIN LIMITS OF WORK TO FINISH GRADE PRIOR TO INSTALLATION OF FINISHED PAVEMENT.
- 15. ROAD AND DRAINAGE CONSTRUCTION SHALL CONFORM TO THE TYPICAL SECTIONS AND DETAILS SHOWN ON THE PLANS AND SHALL MEET LOCAL STANDARDS AND THE REQUIREMENTS OF THE LATEST NHDOT STANDARD SPECIFICATIONS FOR ROADS AND BRIDGE CONSTRUCTION AND THE NHDOT STANDARD STRUCTURE DRAWINGS UNLESS OTHERWISE
- 16. STORMWATER DRAINAGE SYSTEM SHALL BE CONSTRUCTED TO LINE AND GRADE AS SHOWN ON THE PLANS. CONSTRUCTION METHODS SHALL CONFORM TO NHDOT STANDARD SPECIFICATIONS, SECTION 603, CATCH BASINS AND DRAIN MANHOLES SHALL CONFORM TO SECTION 604. ALL CATCH BASIN GRATES SHALL BE TYPE B AND CONFORM TO NHDOT STANDARDS AND SPECIFICATIONS UNLESS OTHERWISE NOTED.
- 17. NO FILL SHALL BE PLACED IN ANY WETLAND AREA WITHOUT A WETLANDS PERMIT.
- 18. ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS IN THE IMMEDIATE AREA.
- 19. ALL DISTURBED AREAS NOT TO BE PAVED OR OTHERWISE TREATED SHALL RECEIVE 6" LOAM, SEED, FERTILIZER, AND MULCH.
- 20. DENSITY REQUIREMENTS:

SHALL NOT POND WATER.

- LOCATION MINIMUM DENSITY*
- 95%* BELOW PAVED OR CONCRETE AREAS 95%** TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL 90%** BELOW LOAM AND SEED AREAS
- ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM DRY DENSITY AT THE OPTIMUM MOISTURE CONTENT. * ASTM D-1557 ** ASTM D-698.

UTILITY NOTES

- 1. LENGTH OF PIPE IS FOR CONVENIENCE ONLY. ACTUAL PIPE LENGTH SHALL BE DETERMINED
- 2. ALL PROPOSED UTILITY WORK, INCLUDING MATERIAL, INSTALLATION, TERMINATION, EXCAVATION, BEDDING, BACKFILL, COMPACTION, TESTING, CONNECTIONS, AND CONSTRUCTION SHALL BE COORDINATED WITH AND COMPLETED IN ACCORDANCE WITH THE APPROPRIATE REQUIREMENTS, CODES, AND STANDARDS OF ALL CORRESPONDING UTILITY ENTITIES AND SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING AND DETERMINING THE LOCATION, SIZE, AND ELEVATION OF ALL EXISTING UTILITIES, SHOWN OR NOT SHOWN ON THESE PLANS, PRIOR TO THE START OF ANY CONSTRUCTION. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES FOUND INTERFERING WITH THE PROPOSED CONSTRUCTION AND APPROPRIATE REMEDIAL ACTION BE AGREED TO BY THE ENGINEER BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTACT "DIGSAFE" (811) AT LEAST 72 HOURS BEFORE DIGGING.
- 4. COORDINATE ALL WORK ADJACENT TO PROPOSED BUILDINGS WITH ARCHITECTURAL BUILDING DRAWINGS. CONFIRM UTILITY PENETRATIONS AND INVERT ELEVATIONS ARE COORDINATED PRIOR TO INSTALLATION.
- 5. THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES OWNING UTILITIES. EITHER OVERHEAD OR UNDERGROUND, WITHIN THE CONSTRUCTION AREA AND SHALL COORDINATE AS NECESSARY WITH THE UTILITY COMPANIES OF SAID UTILITIES. THE PROTECTION OR RELOCATION OF UTILITIES IS ULTIMATELY THE RESPONSIBILITY OF THE CONTRACTOR.
- 6. THE EXACT LOCATION OF NEW UTILITY CONNECTIONS SHALL BE DETERMINED BY THE CONTRACTOR IN COORDINATION WITH UTILITY COMPANY, COUNTY AGENCY, AND/OR PRIVATE
- 7. THE CONTRACTOR SHALL PROVIDE AND INSTALL ALL MANHOLES, BOXES, FITTINGS, CONNECTORS, COVER PLATES, AND OTHER MISCELLANEOUS ITEMS NOT NECESSARILY DETAILED ON THESE DRAWINGS TO RENDER THE UTILITY INSTALLATION COMPLETE AND
- 8. ALL UTILITY COMPANIES REQUIRE INDIVIDUAL CONDUITS. CONTRACTOR TO COORDINATE WITH TELEPHONE, CABLE, AND ELECTRIC COMPANIES REGARDING NUMBER, SIZE, AND TYPE OF CONDUITS REQUIRED PRIOR TO INSTALLATION OF ANY CONDUIT.
- 9. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONDUIT AND WIRING TO ALL SIGNS AND
- LIGHTS. CONDUIT TO BE A MINIMUM OF 24" BELOW FINISH GRADE. 10. ALL PROPOSED UTILITIES SHALL BE UNDERGROUND. ALL UNDERGROUND CONDUITS SHALL
- 11. THE CONTRACTOR SHALL ARRANGE AND PAY FOR ALL INSPECTIONS, TESTING, AND RELATED SERVICES AND SUBMIT COPIES OF ACCEPTANCE TO THE OWNER, UNLESS OTHERWISE
- 12. PROVIDE PERMANENT PAVEMENT REPAIR FOR ALL UTILITY TRENCHES IN EXISTING ROAD OR PAVEMENT TO REMAIN. SAW CUT TRENCH, PAVEMENT, AND GRANULAR BASE THICKNESS TO MATCH EXISTING PAVEMENT. OBTAIN ALL PERMITS REQUIRED FOR TRENCHING.
- 13. UNLESS OTHERWISE SPECIFIED, ALL UNDERGROUND STRUCTURES, PIPES, CHAMBERS, ETC. SHALL BE COVERED WITH A MINIMUM OF 18" OF COMPACTED SOIL BEFORE EXPOSURE TO VEHICLE LOADS.
- 14. THE PROPERTY WILL BE SERVICED BY THE FOLLOWING:
 - DRAINAGE PRIVATE SEWER MUNICIPA

HAVE NYLON PULL ROPES.

WATER MUNICIPAL GAS

SITE PLAN REGULATIONS.

- N/A **FLECTRIC** CONSOLIDATED COMMUNICATIONS TELECOMM
- 17. ALL UTILITIES SHALL BE INSTALLED UNDERGROUND IN ACCORDANCE WITH SECTION 25.02(1) OF THE
- 18. THE CONTRACTOR SHALL OBTAIN UTILITY CONNECTION PERMITS FROM THE ENGINEERING SERVICES DIVISION FOR THE PROPOSED WATER SERVICE, SEWER SERVICE, AND STORM DRAIN CONNECTION(S), IF
- APPLICABLE. INDIVIDUAL PERMITS WILL BE REQUIRED FOR EACH CONNECTION.
- 19. FINAL OVERHEAD ELECTRIC DESIGN BY UNITIL SHALL ACCOMMODATE THE SAFE PASSAGE OF THE CONCORD FIRE DEPARTMENT LADDER TRUCK.



SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

NOTES & LEGEND


UNITIL WEST CONCORD SUBSTATION 1-7 MCGUIRE STREET, CONCORD, NH 03301


OWNED BY/PREPARED FOR UNITIL ENERGY SYSTEMS, INC. 6 LIBERTY LANE WEST, HAMPTON, NH 03824 APPLICANT

UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833

SCALE: NOT TO SCALE

AUGUST 20, 2025





NICHOLAS

GOLON

No. 14086



| 48 Constitution Drive Structural Engineers Bedford, NH 03110 Traffic Engineers Phone (603) 472-4488 and Surveyors Fax (603) 472-9747 andscape Architects www.tfmoran.com

96159-01 CK NG CADFILE 96159-01 COVER & DETAILS DR JB FB C - 02

CONSTRUCTION SEQUENCE NOTES

1. INSTALL STABILIZED CONSTRUCTION ENTRANCE.

2. CUT AND CLEAR TREES WITHIN AREA OF DISTURBANCE UNLESS OTHERWISE NOTED.

3. CONSTRUCT TEMPORARY AND PERMANENT EROSION CONTROL FACILITIES PRIOR TO ANY EARTH MOVING OPERATION.

4. ROUGH GRADE SITE OR PHASED WORK AREA. ALL SLOPES SHALL BE STABILIZED IMMEDIATELY AFTER GRADING. ALL DISTURBED AREAS SHALL BE STABILIZED NO LATER THAN 72 HOURS AFTER CONSTRUCTION ACTIVITY CEASES. IF EARTHWORK TEMPORARILY CEASES ON A PORTION OF OR THE ENTIRE SITE, AND WILL NOT RESUME WITHIN 21 DAYS, THE AREA SHALL BE STABILIZED.

AN AREA SHALL BE CONSIDERED STABILIZED IF:

A) BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;

B) A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED;

C) A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH STONE OR RIPRAP HAS BEEN INSTALLED, OR D) EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

7. CONSTRUCT CULVERTS, DETENTION BASINS AND TREATMENT SWALES. PLACE HEADWALLS, RIP-RAP AND OTHER DRAINAGE FACILITIES ACCORDING TO PLAN. THE CONTRACTOR SHALL STABILIZE ALL DITCHES, SWALES, AND PONDS/BASINS PRIOR TO DIRECTING FLOW TO THEM.

8. INSTALL ALL UNDERGROUND UTILITIES.

9. CONSTRUCT SUBSTATION YARD AND CONTROL HOUSE.

10. CONSTRUCT PARKING AND FINISH GRADE SITE ACCORDING TO PLAN. ALL SLOPES SHALL BE STABILIZED IMMEDIATELY AFTER GRADING.

11. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENTATION CONTROL MEASURES PERIODICALLY AND IMMEDIATELY AFTER STORM EVENTS.

12. COMPLETE PERMANENT SEEDING AND LANDSCAPING.

13. REMOVE TEMPORARY EROSION CONTROL MEASURES ONCE ALL AREAS ARE STABILIZED WITH A SUITABLE STAND OF GRASS, PAVEMENT OR COMPACTED GRAVELS.

* REFER TO THE STORM WATER MANAGEMENT PLAN FOR EROSION CONTROL MEASURES AND SPECIFIC INFORMATION.

GENERAL NOTES

1. ALL IN PAVEMENT MANHOLES SHALL HAVE RIMS SET TO FINISH GRADE REGARDLESS OF ANY ELEVATIONS OTHERWISE

2. WHERE DEPTH OF COVER IS LESS THAN 3 FEET CLASS V REINFORCED CONCRETE PIPE SHALL BE USED.

3. THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES OWNING UTILITIES, EITHER OVERHEAD OR UNDERGROUND, WITHIN THE CONSTRUCTION AREA AND SHALL COORDINATE AS NECESSARY WITH THE UTILITY COMPANIES OF SAID UTILITIES. THE PROTECTION OR RELOCATION OF UTILITIES IS ULTIMATELY THE RESPONSIBILITY OF THE CONTRACTOR.

4. THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY HIS WORK AT ALL TIMES.

5. ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS IN THE IMMEDIATE AREA.

6. EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED FOR THE DURATION OF THE PROJECT IN ACCORDANCE WITH APPLICABLE NHDES STANDARDS. THESE DETAILS SERVE AS A GUIDE ONLY.

7. REFER TO THE TOWN STANDARD DETAILS, LATEST REVISION, FOR ADDITIONAL INFORMATION AND CRITERIA.

8. THE CONTRACTOR SHALL STABILIZE ALL DITCHES, SWALES, AND PONDS PRIOR TO DIRECTING FLOW TO THEM. 9. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5

WINTER CONSTRUCTION

ACRES AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.

IN ADDITION TO THE OTHER NOTES CONTAINED ON THIS PLAN, THE FOLLOWING MUST BE IMPLEMENTED:

. WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED AS SUCH THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.

2. AN AREA WITHIN 100 FEET OF A PROTECTED NATURAL RESOURCE MUST BE PROTECTED WITH A DOUBLE ROW OF SEDIMENT BARRIER.

TEMPORARY MULCH MUST BE APPLIED WITHIN 7 DAYS OF SOIL EXPOSURE OR PRIOR TO ANY STORM EVENT, BUT AFTER EVERY WORKDAY IN AREAS WITHIN 100 FEET FROM A PROTECTED NATURAL RESOURCE.

4. AREAS THAT HAVE BEEN BROUGHT TO FINAL GRADE MUST BE PERMANENTLY MULCHED THE SAME DAY.

5. IN THE EVENT OF A SNOWFALL GREATER THAN 1 INCH (FRESH OR CUMULATIVE), THE SNOW SHALL BE REMOVED FROM THE AREAS DUE TO BE SEEDED AND MULCHED.

6. LOAM SHALL BE FREE OF FROZEN CLUMPS BEFORE IT IS APPLIED.

7. A DITCH THAT WILL BE CONSTRUCTED DURING THE WINTER MUST BE STABILIZED WITH RIPRAP.

OVERWINTER STABILIZATION

. PERMANENT STABILIZATION CONSISTS OF AT LEAST 85% VEGETATION, PAVEMENT/GRAVEL BASE OR RIPRAP.

2. ALL PROPOSED VEGETATED AREAS THAT DO NO EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.

4. AFTER NOVEMBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OR 3 INCHES OF CRUSHED GRAVEL PER NHDOT

5. DO NOT EXPOSE SLOPES OR LEAVE SLOPES EXPOSED OVER THE WINTER OR FOR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY PROTECTED WITH MULCH.

6. APPLY HAY MULCH AT TWICE THE STANDARD RATE (150 LBS. PER 1,000 SF). THE MULCH MUST BE THICK ENOUGH SUCH THAT THE GROUND SURFACE WILL NOT BE VISIBLE AND MUST BE ANCHORED.

7. USE MULCH AND MULCH NETTING OR AN EROSION CONTROL MULCH BLANKET OR MIX FOR ALL SLOPES GREATER THAN 8% OR OTHER AREAS EXPOSED TO DIRECT WIND.

8. INSTALL AN EROSION CONTROL BLANKET IN ALL DRAINAGE WAYS (BOTTOM AND SIDES) WITH A SLOPE

GREATER THAN 3%. 9. SEE THE VEGETATION MEASURES FOR MORE INFORMATION ON SEEDING DATES AND TYPES.

EROSION CONTROL NOTES

DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED:

1. INSTALLATION OF SILTATION FENCES AND OTHER EROSION CONTROL MEASURES SHALL BE COMPLETED PRIOR TO THE START OF SITE WORK IN ANY GIVEN AREA. PREFABRICATED SILTATION FENCES SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

2. SILTATION FENCES AND OTHER EROSION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION AND REMOVED WHEN ALL SLOPES HAVE A VEGETATIVE COVER OF GREATER THAN 85%. EROSION CONTROL MEASURES SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EVERY RAINFALL.

3. EXISTING VEGETATION IS TO REMAIN UNDISTURBED WHEREVER POSSIBLE.

4. THE AREA OF LAND EXPOSED AND THE TIME OF EXPOSURE SHALL BE MINIMIZED. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL GRADING.

5. ALL DISTURBED AREAS SHALL HAVE A MINIMUM OF 4" OF LOAM. ACCEPTABLE SEED MIXES ARE AS FOLLOWS:

TYPICAL LAWN MIX (MIN. 200 LBS/ACRE): 33% CREEPING RED FESCUE (MIN. 66 LBS/ACRE) 42% PERENNIAL RYEGRASS (MIN. 84 LBS/ACRE) 21% KENTUCKY BLUEGRASS (MIN. 42 LBS/ACRE) (MIN. 8 LBS/ACRE)

TEMPORARY LAWN MIX: (MIN. 47 LBS/ACRE)

WILDFLOWER SLOPE (NHDOT TYPE 45) MIX 3:1 OR GREATER SLOPES (MIN. 160 LBS/ACRE):

38% CREEPING RED FESCUE (MIN. 60 LBS/ACRE) 32% PERENNIAL RYEGRASS (MIN. 51 LBS/ACRE) 5% REDTOP (MIN. 8 LBS/ACRE) 5% ALSIKE CLOVER (MIN. 8 LBS/ACRE) 5% BIRDSFOOT TREFOIL (MIN. 8 LBS/ACRE) 3% LANCE-LEAF COREOPSIS (MIN. 3 LBS/ACRE) 3% OXEYE DAISY (MIN. 3 LBS/ACRE) 3% BUTTERFLY WEED (MIN. 3 LBS/ACRE) 3% BLACKEYED SUSAN (MIN. 3 LBS/ACRE) 3% WILD LUPINE (MIN. 3 LBS/ACRE)

GENERAL SLOPE (NHDOT TYPE 44) MIX 3:1 OR GREATER SLOPES (MIN. 160 LBS/ACRE): 44% CREEPING RED FESCUE (MIN. 70 LBS/ACRE)

38% PERENNIAL RYEGRASS (MIN. 60 LBS/ACRE) 6% REDTOP (MIN. 10 LBS/ACRE) 6% ALSIKE CLOVER (MIN. 10 LBS/ACRE) 6% BIRDSFOOT TREFOIL (MIN. 10 LBS/ACRE)

A. PLACING LOAM ON SITE a. ALL SUBGRADE ELEVATIONS SHOULD BE UNIFORMLY GRADED TO RECEIVE LOAM AND SHALL BE INSPECTED AND APPROVED BY THE GENERAL CONTRACTOR PRIOR TO PLACEMENT OF LOAM.

PLACE LOAM TO FORM A MINIMUM DEPTH OF 4" WHEN ROLLED, UNLESS OTHERWISE INDICATED. ALL DEPRESSIONS EXPOSED DURING THE ROLLING SHALL BE FILLED WITH ADDITIONAL LOAM.

SEED BED PREPARATION

AFTER FINISH GRADING AND JUST BEFORE SEEDING, THE AREAS TO BE SEEDED SHALL BE LOOSENED TO PROVIDE A ROUGH, FIRM BUT FINELY PULVERIZED SEEDBED. THE INTENT IS A TEXTURE CAPABLE OF RETAINING WATER, SEED AND FERTILIZER WHILE REMAINING STABLE AND ALLOWING SEED TIME TO GERMINATE. SEED SHALL BE APPLIED TO THE CONDITIONED SEEDBED NOT MORE THAN 48 HOURS AFTER THE SEEDBED HAS BEEN PREPARED.

6. LIME AND FERTILIZER SHALL BE INCORPORATED INTO THE SOIL PRIOR TO OR AT THE TIME OF AT THE TIME OF SEEDING. A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 500 LBS. PER ACRE OF 10-20-20 FERTILIZER SHALL BE APPLIED. SEEDING PRACTICES SHALL COMPLY WITH LOCAL USDA SOIL CONSERVATION SERVICES RECOMMENDATIONS.

7. HAY MULCH OR JUTE MATTING SHALL BE USED WHERE INDICATED ON THE PLANS. A MINIMUM OF 1.5 TONS OF MULCH PER ACRE SHALL BE APPLIED. MULCH SHALL BE ANCHORED IN PLACE WHERE NECESSARY. JUTE MATTING SHALL BE LAID IN THE DIRECTION OF RUNOFF FLOW AND APPLIED IN ACCORDANCE WITH MANUFACTURER'S

8. PERMANENT OR TEMPORARY COVER MUST BE IN PLACE BEFORE THE GROWING SEASON ENDS. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS AREA NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 15 TO SEPTEMBER 15. NO DISTURBED AREA SHALL BE LEFT EXPOSED DURING WINTER MONTHS.

9. WATER SHALL BE USED FOR DUST CONTROL IN APPROPRIATE AREAS.

STOCKPILE NOTES

1. LOCATE STOCKPILES A MINIMUM OF 50 FEET AWAY FROM CONCENTRATED FLOWS OF STORMWATER, DRAINAGE COURSES AND INLETS.

2. PROTECT ALL STOCKPILES FROM STORMWATER RUN-ON USING TEMPORARY PERIMETER MEASURES SUCH AS

DIVERSIONS, BERMS, SANDBAGS OR OTHER APPROVED PRACTICES.

3. STOCKPILES SHOULD BE SURROUNDED BY SEDIMENT BARRIERS, SUCH AS SILT FENCE OR SILT SOCK, TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.

4. IMPLEMENT WIND EROSION CONTROL PRACTICES AS APPROPRIATE ON ALL STOCKPILED MATERIAL.

5. PLACE BAGGED MATERIALS ON PALLETS AND UNDER COVER.

a. INACTIVE SOIL STOCKPILES SHOULD BE COVERED WITH ANCHORED TARPS OR PROTECTED WITH SOIL STABILIZATION MEASURES (TEMPORARY SEED AND MULCH OR OTHER TEMPORARY PRACTICE) AND TEMPORARY PERIMETER SEDIMENT BARRIERS AT ALL TIMES.

b. INACTIVE STOCKPILES OF CONCRETE RUBBLE, ASPHALT CONCRETE RUBBLE, AGGREGATE MATERIALS AND OTHER SIMILAR MATERIALS SHOULD BE PROTECTED WITH TEMPORARY SEDIMENT PERIMETER BARRIERS AT ALL TIMES. IF THE MATERIALS ARE A SOURCE OF DUST, THEY SHOULD ALSO BE

7. ACTIVE STOCKPILES

a. ALL STOCKPILES SHOULD BE SURROUNDED WITH TEMPORARY LINEAR SEDIMENT BARRIERS PRIOR TO THE ONSET OF PRECIPITATION. PERIMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMODATE THE DELIVERY AND REMOVAL OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH

b. WHEN A STORM EVENT IS PREDICTED, STOCKPILES SHOULD BE PROTECTED WITH AN ANCHORED PROTECTIVE COVERING.



SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

NOTES

UNITIL WEST CONCORD SUBSTATION 1-7 MCGUIRE STREET, CONCORD, NH 03301

UNITIL ENERGY SYSTEMS, INC. 6 LIBERTY LANE WEST, HAMPTON, NH 03824

UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833


SCALE:


NICHOLAS

GOLON

No. 14086

AUGUST 20, 2025





48 Constitution Drive ivil Engineers tructural Engineers Bedford, NH 03110 raffic Engineers Phone (603) 472-4488 and Surveyors Fax (603) 472-9747 _andscape Architects cientists www.tfmoran.com

-96159-01 COVER & DETALS


C - 03

48 Constitution Drive, Bedford, N.H. 03110

Copyright 2025 ©TFMoran, Inc.

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of TFMoran, Inc.

This plan is not effective unless signed by a duly authorized officer of TFMoran, Inc.



CB 2017

CB 2217

CB 2464

CB 3124

DMH 1333

DMH 1942

291.01

291.07

257.07

| 286.18 |

280.06

284.17

280.14

252.99

283.33

276.29

283.79 283.96

281.24 280.97

285.20 | 284.37 | 283.88

271.78 | 270.80 | 270.79

266.44

281.47

278.20

271.56

281.74

265.91

WETLAND DELINEATION MANUAL (1987) AND THE REGIONAL

SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND

DELINEATION MANUAL: NORTHCENTRAL AND NORTHEAST

REGION, VERSION 2, JANUARY 2012. DOMINANT HYDRIC

SOILS WITHIN THE WETLAND(S) WERE IDENTIFIED USING

"FIELD INDICATORS OF HYDRIC SOILS OF THE UNITED

HYDROPHYTIC VEGETATION WAS DETERMINED USING THE

SOILS, NRCS, VERSION 8.1, 2017. DOMINANCE OF

3.3 HTTP://WETLAND_PLANTS.USACE.ARMY.MIL.

STATES" A GUIDE FOR IDENTIFYING AND DELINEATING HYDRIC

USACE NATIONAL WETLAND PLANT LIST, NWPL 2016 VERSION

-----W------

____D

——-G——

TREES

SEWER LINE

WATER LINE

DRAIN LINE

OVERHEAD UTILITIES

GAS LINE

BOLLARD

 \geq

TFMoran, Inc.

REV. DATE

9-10-25 | CORRECT CERTAIN ITEMS IN NOTE 10, ADD SEWER

EASEMENT BOOK AND PAGE REFERENCE

DESCRIPTION

CHAIN LINK FENCE

SIGN

GAS VALVE

LIGHT POLE

GUY ANCHOR

ELECTRIC METER

HYDRANT

MRD I MRD


DR CK


cientists


Civil Engineers raffic Engineers Land Surveyors


| 48 Constitution Drive Structural Engineers | Bedford, NH 03110 Phone (603) 472-4488 Landscape Architects Fax (603) 472-9747 www.tfmoran.com


2202 SHEET 1 OF 1 KMRD CADFILE 96159.00 Survey











- 1. IT IS BEING PROPOSED TO RELOCATE THE EXISTING UNITIL WEST CONCORD SUBSTATION.
- 2. TOTAL SITE AREA: 8.66± AC TOTAL AREA OF DISTURBANCE: 2.03± AC
- SOILS SHOWN ARE FROM THE SOIL SURVEY OF MERRIMACK COUNTY, NH, EASTERN PART, PREPARED BY USDA-SOIL CONSERVATION SERVICES. 598B WINDSOR-URBAN LAND COMPLEX 0-8%, HSG B
- 4. STORM WATER DRAINAGE SYSTEM IS SHOWN ON THE PLAN. SEE GRADING & DRAINAGE PLAN FOR RIM, INVERT, PIPE LENGTH, AND SLOPE INFORMATION. POST-CONSTRUCTION RUNOFF COEFFICIENT: C=0.86 IMPERVIOUS SURFACE AREA: 0.72± AC
- STABILIZATION PRACTICES FOR EROSION AND SEDIMENTATION CONTROLS:

TEMPORARY STABILIZATION - TOPSOIL STOCKPILES AND DISTURBED AREAS OF THE CONSTRUCTION SITE THAT WILL NOT BE REDISTURBED FOR 14 DAYS OR MORE MUST BE STABILIZED BY THE 14TH DAY AFTER THE LAST DISTURBANCE. THE TEMPORARY SEED SHALL BE ANNUAL RYE APPLIED AT THE RATE OF 1.1 LBS PER 1,000 SF. PRIOR TO SEEDING, A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 500 LBS PER ACRE OF 10-20-20 FERTILIZER SHALL BE APPLIED. AFTER SEEDING, EACH AREA SHALL BE MULCHED WITH 1.5 TONS PER ACRE OF HAY MULCH. MULCH TO BE ANCHORED IN PLACE WHERE NECESSARY. AREAS OF THE SITE THAT WILL BE PAVED WILL BE TEMPORARILY STABILIZED BY APPLYING GEOTEXTILES AND A STONE SUB-BASE UNTIL BITUMINOUS PAVEMENT CAN BE APPLIED. CALCIUM CHLORIDE SHALL BE USED FOR DUST CONTROL

PERMANENT STABILIZATION - DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASES SHALL BE STABILIZED WITH PERMANENT SEED NO LATER THAN 3 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY. THE PERMANENT SEED MIX SHALL CONSIST OF 0.45 LBS/1,000 SF TALL FESCUE, 0.20 LBS/1,000 SF CREEPING RED FESCUE, AND 0.20 LBS/1,000 SF BIRDSFOOT TREFOIL. PRIOR TO SEEDING, A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 500 LBS PER ACRE IF 10-20-20 FERTILIZER SHALL BE APPLIED. AFTER SEEDING, EACH AREA SHALL BE MULCHED WITH 1.5 TONS PER ACRE OF HAY MULCH. MULCH TO BE ANCHORED IN PLACE WHERE NECESSARY.

6. <u>STRUCTURAL PRACTICES</u> FOR EROSION AND SEDIMENTATION CONTROL

SILT SOCK - WILL BE CONSTRUCTED AROUND THE PERIMETER OF THE DISTURBED AREAS AND WILL DELINEATE THE LIMITS OF WORK FOR THE PROPOSED CONSTRUCTION. THE SILT SOCK WILL BE INSTALLED BY OTHERS. POSTS SHALL BE USED WITH AT LEAST 6" OF THE POST BURIED BELOW THE GROUND SURFACE TO PREVENT THE SILT SOCK FROM FORMING GAPS NEAR THE GROUND SURFACE. RUNOFF WILL FLOW THROUGH THE OPENINGS IN THE SILT SOCK WHILE RETAINING THE SEDIMENT WITHIN THE CONSTRUCTION AREA.

STABILIZED CONSTRUCTION ENTRANCE - WILL BE INSTALLED IN ACCORDANCE WITH THE DETAIL AT THE ENTRANCE TO THE CONSTRUCTION SITE TO HELP REDUCE VEHICLE TRACKING OF SEDIMENTS OFF THE SITE. THE STABILIZED ENTRANCE WILL BE 20'-WIDE AND FLARE AT THE ENTRANCE TO THE PAVED ROAD AND HAVE A DEPTH OF 12" OF STONE. THE STABILIZED ENTRANCE SHALL BE MAINTAINED UNTIL THE REMAINDER OF THE CONSTRUCTION SITE HAS BEEN FULLY STABILIZED. THE PAVED STREET ADJACENT TO THE SITE SHALL BE SWEPT ON A WEEKLY BASIS TO REMOVE EXCESS MUD AND DIRT FROM BEING TRACKED FROM THE SITE. TRUCKS HAULING MATERIAL TO AND/OR FROM THE SITE SHALL BE COVERED WITH A TARPAULIN.

CATCH BASINS - WILL BE CLEANED ON AN ANNUAL BASIS TO REMOVE ALL SEDIMENTS FROM THE CATCH BASIN SUMPS.

CATCH BASIN PROTECTION - WILL BE INSTALLED AT ALL CATCH BASINS WITHIN THE CONSTRUCTION AREA. FILTER FABRIC WILL BE INSTALLED AROUND THE GRATES OF CATCH BASINS THAT ARE LOCATED IN THE TRAVEL WAY AND STONE/FILTER FABRIC PROTECTION WILL BE INSTALLED AT THE CATCH BASINS FOUND WITHIN THE PARKING AREA AND GRASS.

BLANKET SLOPE PROTECTION - SHALL BE INSTALLED ON ALL 2:1 SLOPES OR STEEPER ON SITE. ANCHOR THE TOP OF THE BLANKET BY ANCHORING THE BLANKET IN A 6" DEEP TRENCH. BACKFILL AND COMPACT TRENCH AFTER STAPLING. ROLL THE BLANKET IN THE DIRECTION OF STORM WATER FLOW. WHERE 2 OR MORE STRIPS OF BLANKET ARE REQUIRED, A MINIMUM OF 4" OF OVERLAP SHALL BE PROVIDED.

STONE CHECK DAMS - WILL BE INSTALLED IN EXISTING AND PROPOSED GRASS SWALES TO REDUCE THE VELOCITY OF CONCENTRATED STORM WATER FLOWS AND PREVENT EROSION OF THE

7. STORM WATER MANAGEMENT

STORMWATER DRAINAGE FOR THE SUBSTATION AREA WILL BE COLLECTED BY AN OPEN AND CLOSED DRAINAGE SYSTEM. WHEN CONSTRUCTION IS COMPLETE, THE MAJORITY OF THE SITE WILL DRAIN INTO A FILTRATION BASIN.

- 8. ALL CONSTRUCTION DEBRIS AND WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURE DUMPSTERS OR APPROVED ENCLOSURE AND REMOVED FROM THE SITE ON A WEEKLY BASIS. NO CONSTRUCTION WASTE SHALL BE BURIED ON SITE. PORTABLE TOILET SANITARY WASTE FACILITIES WILL BE PROVIDED DURING CONSTRUCTION AND MAINTAINED/DISPOSED OF ON A REGULAR BASIS IN ACCORDANCE WITH TOWN AND STATE REGULATIONS
- 9. A LIST OF CONSTRUCTION ITEMS AND OTHER PRODUCTS USED ON THIS PROJECT SHALL BE KEPT ON RECORD WITH THIS PLAN ONSITE. ALL CHEMICALS, PETROLEUM PRODUCTS AND OTHER MATERIALS USED DURING CONSTRUCTION SHALL BE STORED IN A SECURE AREA, AND PRECAUTIONS USED TO PREVENT POTENTIAL SOURCES OF CONTAMINATION OR POLLUTION. ANY SPILL OF THESE TYPES OF SUBSTANCES SHALL BE CLEANED UP AND DISPOSED OF IN A LEGAL MANNER AS SPECIFIED BY STATE REGULATIONS AND THE MANUFACTURER. ANY SPILL IN AMOUNTS EQUAL TO OR EXCEEDING REPORTABLE QUANTITY AS DEFINED BY THE EPA SHALL TAKE THE
- NOTIFY THE NATIONAL RESPONSE CENTER IMMEDIATELY AT (888) 424-8802; IN WASHINGTON, D.C., CALL (202) 426-2675. - WITHIN 14 DAYS, SUBMIT A WRITTEN DESCRIPTION OF THE RELEASE TO THE EPA REGIONAL
- OFFICE PROVIDING THE DATE AND CIRCUMSTANCES OF THE RELEASE AND THE STEPS TO BE TAKEN TO PREVENT ANOTHER RELEASE - MODIFY THE POLLUTION PREVENTION PLAN TO INCLUDE THE INFORMATION LISTED ABOVE

- GOOD HOUSEKEEPING:
 THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ONSITE DURING THE CONSTRUCTION PROJECT.
- AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO DO THE JOB; - ALL MATERIALS STORED ONSITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE; - PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S
- SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE
- WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE
- MANUFACTURERS' RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE FOLLOWED; - TRASH DUMPSTERS SHALL BE GASKETED OR HAVE A SECURE WATERTIGHT LID AND BE PLACED AWAY FROM STORMWATER CONVEYANCES AND DRAINS

LEGEND




INLET PROJECTION

REV DATE



STABILIZED CONSTRUCTION ENTRANCE



MATERIALS ONSITE.

- HESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS: - PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE: - ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED; THEY CONTAIN IMPORTANT PRODUCT INFORMATION:
- IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED.

FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ON SITE:

ALL ONSITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER, ONCE APPLIED, FERTILIZER WILL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO STORM WATER. STORAGE WILL BE IN A COVERED SHED. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER WILL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS.

ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS.

EXCESS CONCRETE SHALL BE USED IN AREAS DESIGNATED BY THE SITE CONTRACTOR. WASH WATER SHALL BE DISPOSED OF USING BEST MANAGEMENT PRACTICES. BUILDING CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL DRUM WASH WATER ASSOCIATED WITH CONCRETE FOR THE BUILDING PAD. SITE CONTRACTOR TO COORDINATE AND PROVIDE BUILDING CONTRACTOR WITH AN AREA FOR DRUM WASH WATER.

- N ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL
- MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.
- MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ONSITE. EQUIPMENT AND MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST, AND
- PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE. - ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY. - THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE.
- SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF SIZE. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER
- ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED - THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY—TO—DAY SITE OPERATIONS, WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. THEY WILL DESIGNATE AT LEAST THREE OTHER SITE PERSONNEL WHO WILL EACH RECEIVE SPILL PREVENTION AND CLEANUP TRAINING. THESE INDIVIDUALS WILL EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE NAMES OF RESPONSIBLE SPILL PERSONNEL WILL BE POSTED IN
- 11. THE CONTRACTOR IS RESPONSIBLE TO MAINTAIN RECORDS OF CONSTRUCTION ACTIVITIES, INCLUDING DATES OF MAJOR GRADING ACTIVITIES, DATES WHEN CONSTRUCTION ACTIVITIES HAVE TEMPORARILY CEASED ON A PORTION OF THE SITE, DATES WHEN WORK IS COMPLETED ON A PORTION OF THE SITE, AND DATES WHEN STABILIZATION MEASURES ARE INITIATED ONSITE.
- 12. THE CONTRACTOR SHALL PERFORM INSPECTIONS OR HAVE A CONSULTING ENGINEER PERFORM INSPECTIONS EVERY SEVEN (7) DAYS AND WITHIN 24 HOURS AFTER A STORM OF 0.5" OR GREATER. INSPECTIONS REPORTS ARE TO BE KEPT ON FILE AT THE SITE WITH THIS PLAN. MAINTENANCE OR MODIFICATION SHALL BE IMPLEMENTED AND ADDED TO THE PLAN AS RECOMMENDED BY THE QUALIFIED INSPECTOR.

THE MATERIAL STORAGE AREA AND IN THE OFFICE TRAILER ONSITE.



SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

STORMWATER MANAGEMENT PLAN UNITIL WEST CONCORD SUBSTATION 1-7 MCGUIRE STREET, CONCORD, NH 03301

OWNED BY/PREPARED FOR UNITIL ENERGY SYSTEMS, INC. 6 LIBERTY LANE WEST, HAMPTON, NH 03824

UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833

SCALE: 1"=30"

AUGUST 20, 2025



Structural Engineers raffic Engineers and Surveyors andscape Architects 48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com

96159-01 | CK | NG | CADFILE | 96159-01 | DESIGN_LAYOUT C - 08

1 9/22/25 REVISED PER CITY COMMENTS

DESCRIPTION


DR CK


without the prior written permission of TFMoran, Inc.


TFMoran, Inc.


This plan is not effective unless signed by a duly authorized officer of

HORIZONTAL SCALE 1"=30'










- 1. STONE SIZE 3" COARSE AGGREGATE.
- 2. THICKNESS 6" MIN
- 5. FILTER CLOTH WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE.
- 6. LENGTH NOT LESS THAN 50'. EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30' MIN LENGTH WOULD APPLY.
- 7. WIDTH 10' MIN, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
- 8. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD
- CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE.

 9. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS—OF—WAY MUST BE REMOVED IMMEDIATELY.
- 10. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 11. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

L						
	NO.	REVISION	DATE	City of Concord Engineering Services Division	SECTION: F	EPSC
	-	ı				
	-	_	_	CONSTRUCTION ENTRANCE	DRAWING NO.	E-1
	-	-	_	DETAIL	DATE.	PAGE: 4
	-	_	T = T	22	DATE: 01/08	1




CONSTRUCTION REQUIREMENTS

- 1. LAY FIRST COURSE OF BLOCK ON ITS SIDE FOR DEWATERING. PLACE BLOCKS AGAINST FRAME FOR SUPPORT.
- 2. PLACE HARDWARE CLOTH OR WIRE MESH OVER BLOCK OPENINGS TO SUPPORT STONE.
 3. PLACE STONE ON A 2:1 OR FLATTER SLOPE UP TO THE TOP OF BLOCK.
- PLACE STONE ON A 2:1 OR FLATTER SLOPE UP TO THE TOP OF BLOCK.
 REMOVE STONE AND BLOCKS, AS DIRECTED, WHEN NO LONGER NEEDED. BEFORE STONE AND BLOCKS ARE REMOVED, STABILIZE ANY SEDIMENT WHICH IS PERMITTED TO STAY IN

PLACE WITH VEGETATION.


NO.	REVISION	DATE	City of Concord Engineering Services Division	SECTION: EPSC
-	ı	_		
-	-	_	STONE & BLOCK GRATE	DRAWING E-2
-	ı	_	INLET PROTECTION DETAILS	DATE: 01/09 PAGE: 1
1	_		THEE THOTESTICK BETTHES	1 1 1 1 1 1 1 1 1 1



SAWCUT REQUIREMENTS

DRAWING NO. 11.1

MULTIPLE 12.1




- 1. BEGIN AT THE TOP OF BLANKET INSTALLATION AREA BY ANCHORING BLANKET IN A 6" DEEP TRENCH. BACKFILL AND COMPACT TRENCH AFTER STAPLING.
- 2. ROLL THE BLANKET DOWN THE SWALE IN THE DIRECTION OF THE WATER FLOW.
- 3. THE EDGES OF BLANKETS MUST BE STAPLED WITH APPROX. 4 INCH OVERLAP WHERE 2 OR MORE STRIP WIDTHS ARE REQUIRED.
- 4. WHEN BLANKETS MUST BE SPLICED DOWN THE SWALE, PLACE BLANKET END OVER END WITH 6 INCH (MIN.) OVERLAP AND ANCHOR DOWN SLOPE BLANKET IN A 6 INCH DEEP TRENCH.
- 5. BLANKET SHALL BE NORTH AMERICAN GREEN SC-150 OR APPROVED EQUAL.

BLANKET SLOPE PROTECTION

EROSION CONTROL FOR SLOPE GREATER THAN 5' IN HEIGHT

NOT TO SCALE




THE ENGINEER.

SILT SOCK

NOT TO SCALE

4. COMPOST MATERIAL SHALL BE DISPERSED ON SITE, AS DETERMINED BY



NOT TO SCALE



SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

DETAILS


UNITIL WEST CONCORD SUBSTATION
1-7 MCGUIRE STREET, CONCORD, NH 03301

OWNED BY/PREPARED FOR UNITIL ENERGY SYSTEMS, INC.
6 LIBERTY LANE WEST, HAMPTON, NH 03824
APPLICANT

UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833

SCALE: NOT TO SCALE

AUGUST 20, 2025




NICHOLAS

GOLON

No. 14086

R-12

DATE: 12/08



Civil Engineers
Structural Engineers
Traffic Engineers
Land Surveyors
Landscape Architects
Scientists


48 Constitution Drive
Bedford, NH 03110
Phone (603) 472-4488
Fax (603) 472-9747
www.tfmoran.com


D1 DR FB 96159-01 COVER & DETA LS D-01


Copyright 2025 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110


All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of TFMoran, Inc.


This plan is not effective unless signed by a duly authorized officer of TFMoran, Inc.















NOT TO SCALE




CONCRETE PAD

NOT TO SCALE



NOT TO SCALE



\$\mathcal{G}\$ Unitil

SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

DETAILS

UNITIL WEST CONCORD SUBSTATION
1-7 MCGUIRE STREET, CONCORD, NH 03301

OWNED BY/PREPARED FOR UNITIL ENERGY SYSTEMS, INC.
6 LIBERTY LANE WEST, HAMPTON, NH 03824

APPLICANT


UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833

SCALE: NTS

AUGUST 20, 2025

48 Constitution Drive

1	9/22/25 <i>DATE</i>	REVISED PER CITY COMMENTS	JB	NG	
REV	DATE	DESCRIPTION DESCRIPTION	DR	CK	




Civil Engineers
Structural Engineers
Traffic Engineers
Land Surveyors
Landscape Architects
Scientists

Bedford, NH 03110
Phone (603) 472-4488
Fax (603) 472-9747
www.tfmoran.com

Copyright 2025 ©TFMoran, Inc.
48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of TFMoran, Inc.


This plan is not effective unless signed by a duly authorized officer of TFMoran, Inc.



FILTRATION BASIN NOTES

- 1. THE INSTALLER SHALL NOT ALLOW ANY VEHICULAR OR CONSTRUCTION EQUIPMENT TRAVEL TO OCCUR ACROSS THE PROPOSED BASIN AREA AT ANY TIME EXCEPT DURING EXCAVATION OF TOPSOIL, SUBSOIL AND OTHER MATERIALS NOT SUITABLE FOR BED BOTTOM CONDITIONS.
- 2. CAUTION SHOULD BE EXERCISED DURING SITE PREPARATION TO AVOID COMPACTION OF THE INFILTRATIVE SURFACE.
- NEW ENGLAND ROADSIDE MATRIX WET MEADOW SEED MIX (MIN. 35 LBS/ACRE)
- 4. FILTER MEDIA SOIL SAMPLE TO BE PROVIDED TO THE ENGINEER PRIOR TO PLACEMENT. ON SITE MIXING OF MANUFACTURED SOIL MAY BE ACCEPTABLE PENDING ENGINEER APPROVAL.
- 5. DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE BASIN.
- 6. AFTER THE BASIN IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG.
- 7. VEGETATION SHOULD BE ESTABLISHED IMMEDIATELY.
- 8. DO NOT PLACE FILTRATION SYSTEMS INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.
- 9. FILTRATION MEDIA SHALL BE INSTALLED ALONG INTERIOR SIDE SLOPES TO ELEVATION EQUAL TO OUTLET STRUCTURE RIM OR WEIR ELEVATION, WHICHEVER IS LOWER.
- 10. FILL TO BRING EMBANKMENT AREAS TO GRADE SHALL BE EXISTING SIDE MATERIALS OR IMPORTED MATERIAL CONSISTENT WITH THE GEOTECHNICAL REPORT RECOMMENDATIONS FOR COMMON FILL (SEE NOTE 21 AND 22 ON SHEET C-02).

11. FILTER MEDIA SHALL BE PLACED IN BOTTOM OF SEDIMENT FOREBAY.



1-1/2" CRUSHED GRANITE 7590al NON-WOVEN GEOTEXTILE ್ಕ BANK RUN GRAVEL FABRIC (MIRAFI 140N OR — UNITIL GROUNDING GRID EQUAL) OVERLAP AT TOP (DEPTH 18"±) 12" MIN. CRUSHED GRAVEL FREE DRAINING 3/4" STONE/GRAVEL ─ CONDUITS (DEPTH 24"±) 6" PERF. HDPE PIPE SUITABLE SUBGRADE

UNDER DRAIN TRENCH

l(300mm


NOT TO SCALE

—FINISHED GRADE

(SEE PLAN)

FILTRATION BASIN

NOT TO SCALE



FILTRATION BASIN # 285.5 286.0

NOT TO SCALE

TOP OF BERM INFILTRATION BASIN PLAN VIEW ←RIP-RAP INFILTRATION BASIN SECTION A-A WIDTH (SEE PLAN) TOP OF BERM 12" DEPTH OF STONE (USE NHDOT CLASS C STONE)

CONSTRUCTION SPECIFICATIONS

PREPARE BEDDING: BACKFILL MATERIAL AROUND THE END SECTION MAY BE THE SAME AS THE MATERIAL AROUND THE PIPE, PLACE A FEW INCHES OF BACKFILL MATERIAL IN THE TRENCH OR DITCH WHERE THE END SECTION WILL BE PLACED. COMPACT AND CONTOUR THIS BEDDING MATERIAL TO GENERALLY MATCH THE END SECTION, EXCAVATE AN AREA IN THE BEDDING WHERE TOE TROUGH WILL SEAT SO THAT THE END SECTION WILL BE LEVEL WITH THE BOTTOM OF THE TRENCH OR DITCH IN THE FINISHED INSTALLATION.

PLACE END SECTION OF PIPE: OPEN THE END SECTION COLLAR AND SEAT IT OVER THE TWO PIPE CONNECTIONS. ONCE THE END

SECTION IS POSITIONED, CHECK TO MAKE SURE THAT THE INVERT OF THE END SECTION MATCHES THE INVERT OF THE PIPE AND THAT THE END SECTION IS LEVEL WITH THE TRENCH OR DITCH BOTTOM. SECURE THE END SECTION:


SLIP THE STAINLESS STEEL ROD THROUGH THE PRE-DRILLED HOLES AT THE TOP OF THE COLLAR. THE ROD SHOULD BE BETWEEN THE CROWNS OF THE TWO PIPE CONNECTIONS. PLACE A WASHER ON EITHER END OF THE ROD. PLACE A NUT ON EITHER END OF THE ROD AND TIGHTEN WITH A

SECURE THE TOE TROUGH:

TO PREVENT WASHOUTS FROM HIGH VELOCITY FLOW, IT IS RECOMMENDED THAT THE TROUGH BE SECURED WITH CONCRETE. POUR CONCRETE IN THE TROUGH UP TO THE LEVEL OF THE TRENCH OR DITCH BOTTOM AND ALONG THE ENTIRE LENGTH OF THE TROUGH.

FINISH BACKFILL:

SHOVEL BACKFILL AROUND THE END SECTION IN 6 TO 9 INCH LAYERS EQUALLY ON BOTH SIDES, KNIFING IT TO ELIMINATE VOIDS. TAMP WITH A SMALL-FACED COMPACTOR OR OTHER EQUIPMENT SUITABLE FOR SMALL AREAS. CONTINUE PLACING, KNIFING, AND COMPACTING BACKFILL LAYERS TO THE TOP OF THE END SECTION TO SEAT IT WELL INTO THE BACKFILL.



	DIMENSIONS, INCHES (mm)							
PIPE DIAMETER	PART NO.	A, ±1 (25)	В МАХ	H, ±1 (25)	L, ±1/2 (13)	W, ±2 (50)		
12", 15" (300,375)	1210 NP	6.5 (165)	10 (254)	6.5 (165)	25 (635)	29 (736)		
18" (450)	1810 NP	7.5 (190)	15 (380)	6.5 (168)	32 (812)	35 (890)		
24" (600)	2410 NP	7.5 (190)	18 (450)	6.5 (165)	36 (900)	45 (1140)		
30" (750)	3010 NP	10.5 (266)	NA	7.0 (178)	53 (1346)	68 (1725)		
36" (900)	3610 NP	10.5 (266)	NA	7.0 (178)	53 (1346)	68 (1725)		

FLARED END SECTION

HIGH DENSITY POLYETHYLENE (HDPE)

FLARED END SECTION F.E.S. TYPE I GEOTEXTILE — 12" (MIN.) DEPTH OF STONE HEADWALL


CONSTRUCTION SPECIFICATIONS:

THE SUBGRADE FOR THE GEOTEXTILE FABRIC AND RIP-RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.

- 2. THE ROCK USED FOR RIP-RAP SHALL CONFORM TO NHDOT CLASS C STONE. D50 = 6"
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP—RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- 4. STONE FOR THE RIP-RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

OUTLET APRON

NOT TO SCALE REV DATE **DESCRIPTION** DR CK





SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

DETAILS

UNITIL WEST CONCORD SUBSTATION 1-7 MCGUIRE STREET, CONCORD, NH 03301

UNITIL ENERGY SYSTEMS, INC. 6 LIBERTY LANE WEST, HAMPTON, NH 03824

UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833

SCALE: NTS

AUGUST 20, 2025

NOT TO SCALE




SPILLWAY

Copyright 2025 ©TFMoran, Inc. 48 Constitution Drive, Bedford, N.H. 03110 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of TFMoran, Inc. This plan is not effective unless signed by a duly authorized officer of

BROAD CRESTED WEIR

FROM FOREBAYS NOT TO SCALE



TYPICAL SUBSTATION CROSS SECTION


NOT TO SCALE

COMPLETED.

REQUIREMENTS.

SEE SPECIFICATIONS FOR OBSERVATION PROCESS AND

DETAIL DEVELOPED BY THE <u>URBAN TREE FOUNDATION</u> AND IS OPEN SOURCE AND FREE TO USE BY OTHERS.





- FINISHED GRADE

CONDUIT (2" & 3")

 \sim CONDUIT (5")

6" 1-1/2" CRUSHED GRANITE

6" BANK RUN GRAVEL

12" CRUSHED GRAVEL

SUITABLE SUBGRADE

TYPICAL NEW YARD AREA SECTION

1. FINAL DESIGN IS TO BE COORDINATED WITH THE OWNER.

SPECIFICATIONS PRIOR TO DELIVERY & INSTALLATION.

Copyright 2025 ©TFMoran, Inc.

TFMoran, Inc.

48 Constitution Drive, Bedford, N.H. 03110

without the prior written permission of TFMoran, Inc.


All rights reserved. These plans and materials may not be copied,

duplicated, replicated or otherwise reproduced in any form whatsoever

This plan is not effective unless signed by a duly authorized officer of

2. CONTRACTOR TO COORDINATE LOCATION OF GROUNDING GRID WITH UNITIL.

3. SAMPLE OF CRUSHED GRANITE SHALL BE PROVIDED BY CONTRACTOR. UNITIL WILL HAVE SAMPLE TESTED TO VERIFY RESISTANCE MEETS



NEVER CUT LEADER ----

DO NOT HEAVILY PRUNE TREE -

AT PLANTING PRUNE ONLY

GUY MATERIAL AT TREE -

CO-DOMINANT LEADERS, AND

DAMAGED OR DEAD BRANCHES

GUY MATERIAL VERTICAL STAKES-

WHERE THE ROOTS BEGIN TO THE

STAKE TO BE 18" BELOW TREE -

NECESSITY OF GUYING AND STAKING.

4. TREE SHALL BE SET PLUMB, AFTER SETTLEMENT.

ONLY WRAP TREE TRUNKS AS REQUIRED BY LANDSCAPE ARCHITECT.

ALL NURSERY TAGS, TAPE, AND SIMILAR MATERIALS SHALL BE REMOVED.

FROM ONE SIDE, AND/OR

GROW TANGENT TO TRUNK

1 9/22/25

REV DATE

PIT IN UNDISTURBED GROUND

BRANCH FROM THE TRUNK)

TRUNK FLARE AND TOP OF -

ROOTBALL SHOULD BE AT

GRADE (TRUNK FLARE IS

ARCHITECT.

NOTES

STRUCTURAL ROOTS PRIMARILY

REJECTABLE

GROW TO ONE SIDE

CROSS OVER LIMBS.

1/2 UP TREE OR TO

WHICHEVER IS LOWER

FIRST BRANCH,

DETAILS L-7, L-8 AS

BURLAP FROM

TRUNK

-SEE ROOT

VARIES


3X ROOTBALL DIAMETER MIN

OBSERVATION

DETAIL L-9

ROOTBALL.

APPLICABLE





SITE DEVELOPMENT PLANS

TAX MAP 494Z LOT 44

DETAILS

UNITIL WEST CONCORD SUBSTATION 1-7 MCGUIRE STREET, CONCORD, NH 03301


UNITIL ENERGY SYSTEMS, INC. 6 LIBERTY LANE WEST, HAMPTON, NH 03824

UNITIL ENERGY SYSTEMS, INC. 30 ENERGY WAY, EXETER, NH 03833

SCALE: NOT TO SCALE

AUGUST 20, 2025


D - 04



Structural Engineers Traffic Engineers and Surveyors andscape Architects

48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747 www.tfmoran.com

96159-01 CK NG CADFILE 96159-01 COVER & DETAILS



REVISED PER CITY COMMENTS

DESCRIPTION