# SITE MODIFICATIONS FOR SITE PLAN COMPLIANCE

# 119 OLD TURNPIKE ROAD CONCORD, NH TAX MAP 751Z LOT 24

OWNER AND APPLICANT


CORNERSTONE REALTY HOLDING INC.

SITE ENGINEER

NOBIS GROUP. - CONCORD, NH

SURVEYOR

RICHARD D. BARTLETT & ASSOCIATES. LLC - CONCORD, NH



APRIL 16, 2025


UNDER THE PROVISIONS OF R.S.A. 674:35 & R.S.A. 674:36

CITY PLANNING BOARD

CITY OF CONCORD, NEW HAMPSHIRE

in accordance with vote of the board dated:

Approval of this plan is limited to the lots as shown



# SHEET INDEX

I.D. <u>NO.</u> <u>DRAWING NAME</u>

S COVER SHEET


G-1 1 GENERAL NOTES AND LEGEND

S-1 2 EXISTING CONDITIONS PLAN

C-1 3 PROPOSED SITE PLAN

100 119 Old Turnpike Road Concord, NH\CAD\DWG\100960.000-C-001-COVER.dwg 4/15/

NOBIS PROJECT NO. 100960.00



## **GENERAL NOTES:**

- 1. EXISTING CONDITIONS, TOPOGRAPHICAL INFORMATION, NORTH ORIENTATION, NORTH ARROW, AND COORDINATE VALUES DEPICTED ON THESE DRAWINGS ARE BASED ON PLANS TITLED "EXISTING CONDITIONS PLAT", DATED NOVEMBER 2024 BY RICHARD D. BARTLET AND ASSOCIATES LLC
- 2. THESE DRAWINGS AND ACCOMPANYING TEXT HAVE BEEN PREPARED FOR MINOR SITE PLAN, FOR REVIEW BY THE CITY OF CONCORD PLANNING BOARD, CODE ENFORCEMENT, GENERAL SERVICES, POLICE, AND FIRE DEPARTMENTS. 3. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE CITY OF CONCORD'S CONSTRUCTION STANDARDS AND DETAILS (LATEST EDITION), AND CITY STANDARDS SHALL TAKE PRECEDENCE IN CASE OF ANY DETAILS OR PLANS IN

- 1. ALL OBSERVATIONS OF THREATENED OR ENDANGERED SPECIES ON THE PROJECT SHALL BE REPORTED IMMEDIATELY TO THE NHF&G NONGAME AND ENDANGERED WILDLIFE ENVIRONMENTAL REVIEW PROGRAM BY PHONE AT 603-271-2461 AND BY EMAIL AT NHFGreview@wildlife.nh.gov, WITH THE EMAIL SUBJECT LINE CONTAINING THE NHB DATACHECK TOOL
- RESULTS LETTER ASSIGNED NUMBER, THE PROJECT NAME, AND THE TERM WILDLIFE SPECIES OBSERVATION. 2. PHOTOGRAPHS OF THE OBSERVED SPECIES AND NEARBY ELEMENTS OF HABITAT OR AREAS OF LAND DISTURBANCE
- SHALL BE PROVIDED TO NHF&G IN DIGITAL FORMAT AT THE ABOVE EMAIL ADDRESS FOR VERIFICATION, AS FEASIBLE. 3. IN THE EVENT A THREATENED OR ENDANGERED SPECIES IS OBSERVED ON THE PROJECT SITE DURING THE TERM OF THE PERMIT, THE SPECIES SHALL NOT BE DISTURBED, HANDLED, OR HARMED IN ANY WAY PRIOR TO CONSULTATION WITH NHF&G AND IMPLEMENTATION OF CORRECTIVE ACTIONS RECOMMENDED BY NHF&G, IF ANY, TO ASSURE THE PROJECT DOES NOT APPRECIABLY JEOPARDIZE THE CONTINUED EXISTENCE OF THREATENED AND ENDANGERED
- SPECIES AS DEFINED IN FIS 1002.04 4. THE NHF&G, INCLUDING IT EMPLOYEES AND AUTHORIZED AGENTS, SHALL HAVE ACCESS TO THE PROPERTY DURING THE TERM OF THE PERMIT.

# **EROSION CONTROL NOTES:**

CATCH BASINS: CARE SHOULD BE TAKEN TO ENSURE THAT SEDIMENTS DO NOT ENTER CATCH BASINS DURING EXCAVATION FOR PIPE TRENCHES, DITCHES AND SWALES. THE CONTRACTOR SHOULD PLACE NON-WOVEN GEOTEXTILE FABRIC FOR INLET PROTECTION OVER INLETS IN AREAS OF SOIL DISTURBANCE, WHICH ARE SUBJECT TO SEDIMENT CONTAMINATION.

PLACE INLET PROTECTION DEVICES, IN CATCH BASINS AND MAINTAIN UNTIL ALL CONSTRUCTION ACTIVITIES HAVE CEASED AND THE SURROUNDING AREAS ARE WELL VEGETATED.

EARTH DISTURBANCE IS EXPECTED FOR THIS PROJECT.

THIS WORK IS ANTICIPATED TO BEGIN IN THE SUMMER OF 2025 WITH A FINAL COMPLETION DATE IN FALL OF 2025 NO WINTER

ADEQUATE MEASURES SHOULD BE TAKEN TO MINIMIZE AIR BORNE DUST PARTICLES ARISING FROM SOIL DISTURBANCE AND CONSTRUCTION.

DISTURBANCE OF AREAS SHOULD BE MINIMIZED AND NOT EXCEED 100,000 SQUARE FEET IN AREA AT ANY ONE TIME. \* NO DISTURBED AREA SHOULD BE LEFT UNSTABILIZED FOR LONGER THAN TWO WEEKS DURING THE GROWING SEASON. \* PERMANENT EROSION CONTROL FEATURES SHOULD BE INCORPORATED INTO THE PROJECT AT THE EARLIEST PRACTICABLE TIME, AS SPECIFIED ON THE CONTRACT PLANS..

\* AS WORK PROGRESSES, PATCH SEEDING AND MULCHING SHOULD BE DONE AS REQUIRED ON AREAS PREVIOUSLY TREATED TO MAINTAIN OR ESTABLISH PROTECTIVE COVER. \* REMOVE ACCUMULATED SEDIMENTS AND DEBRIS WHEN SEDIMENT CONTAINMENT DEVICES REACH 33% CAPACITY.

EROSION CONTROL MEASURES SHALL BE IMPLEMENTED, AS WRITTEN HEREIN AND AS DEPICTED ON THE ACCOMPANYING PLAN, FROM THE COMMENCEMENT OF CONSTRUCTION ACTIVITY UNTIL FINAL STABILIZATION IS COMPLETE:

MULCH: MULCHING WITH LOOSE HAY OR STRAW, AT A RATE OF 2 TONS PER ACRE, SHALL BE DONE IMMEDIATELY AFTER EACH AREA HAS BEEN FINAL GRADED. WHEN SEED FOR EROSION CONTROL IS SOWN PRIOR TO PLACING THE MULCH, THE MULCH SHOULD BE PLACED ON THE SEEDED AREAS WITHIN 48 HOURS AFTER SEEDING.

TACKIFIER: PLACEMENT OF SOIL TACKIFIER HAS PROVEN TO BE AN EFFECTIVE METHOD OF PREVENTING SOIL AND ADHERING MULCH IN PLACE. THE PLACEMENT OF A SOIL TACKIFIER SHOULD BE PERFORMED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS AND SHOULD BE REAPPLIED AS NECESSARY TO CONTROL AIR BORN DUST AND SOIL, AND MULCH LOSS UNTIL PERMANENT VEGETATION IS ESTABLISHED.

ROAD CLEANING: THE CONTRACTOR SHALL SWEEP ROADS DAILY, OR AS NEEDED TO MAINTAIN CLEAN PAVED SURFACES AT ALL CONSTRUCTION ACCESS/EGRESS POINTS.

<u>DUST CONTROL</u>: THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL MEASURES AS NEEDED TO PREVENT AIRBORNE DUST PARTICLES FROM LEAVING THE SITE. DUST CONTROL MEASURES SHALL CONSIST OF USE OF A WATER TRUCK EQUIPPED WITH A SPRAY-BAR THAT DISSIPATES THE WATER EVENLY OVER THE SURFACE.

PERMANENT STABILIZATION: GRASS, TREES, SHRUBS AND MULCHED PLANTING BEDS WILL BE CONSTRUCTED AND MAINTAINED IN LOCATIONS AS SHOWN ON THE DRAWINGS TO STABILIZE AREAS NOT WITHIN THE PARKING LOT/BUILDING FOOTPRINT. THE CONTRACTOR WILL BE RESPONSIBLE FOR EROSION AND SEDIMENT CONTROL FOR ONE YEAR AFTER

# AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

- 1. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED; 2. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED:
- 3. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIP RAP HAS BEEN INSTALLED; 4. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- ALL ROADWAYS/PARKING AREAS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

CONSTRUCTION SHALL BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

SHOULD EXCAVATION DEWATERING BE REQUIRED, THE CONTRACTOR MUST INSURE THAT ANY EXCAVATION DEWATERING DISCHARGES ARE NOT CONTAMINATED. NOTE: THE WATER IS CONSIDERED UNCONTAMINATED IF THERE IS NO GROUNDWATER CONTAMINATION WITHIN 1,000 FEET OF THE DISCHARGE.

THE CONTRACTOR MUST TREAT ANY UNCONTAMINATED EXCAVATION DEWATERING AS NECESSARY TO REMOVE SUSPENDED SOLIDS AND TURBIDITY DURING CONSTRUCTION. THE DISCHARGES MUST BE SAMPLED AT A LOCATION PRIOR TO MIXING WITH STORM WATER OR STREAM FLOW AT LEAST ONCE PER WEEK DURING WEEKS WHEN DISCHARGES OCCUR. THE SAMPLES MUST BE ANALYZED FOR TOTAL SUSPENDED SOLIDS (TSS) AND MUST MEET MONTHLY AVERAGE AND MAXIMUM DAILY TSS LIMITATIONS OF 50 MILLIGRAMS PER LITER (MG/L), RESPECTIVELY.

# SPECIFICATIONS FOR TEMPORARY AND PERMANENT SEEDING:

GRASS SEED MIXES SHALL CONSIST OF THE MIXTURES AS DETAILED IN THE FOLLOWING

EROSION CONTROL SEED MIX				
SEED	BY % MASS	% GERMINATION (MIN.)		
WINTER RYE 80 (MIN.)	80 (MIN.)	85		
RED FESCUE (CREEPING)	4 (MIN.)	80		
PERENNIAL RYE GRASS	3 (MIN.)	90		
RED CLOVER	3 (MIN.)	90		
OTHER CROP GRASS	0.5 (MAX.)			
NOXIOUS WEED SEED	0.5 (MAX.)			
INERT MATTER	1.0 (MAX.)			

PERMANENT SEED MIX RED FESCUE (CREEPING) KENTUCKY BLUE PERENNIAL RYE GRASS LANDINO CLOVER

# WINTER CONSTRUCTION NOTES

ALL PROPOSED POST-DEVELOPMENT VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE ELSEWHERE. MULCH REMAINING IN THE SPRING SHALL BE REMOVED AND REPLACED AT RATE OF 2 TONS PER ACRE. THE PLACEMENT OF EROSION CONTROL BLANKETS OR MULCH AND TACKIFIER SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND.

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.

AFTER OCTOBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES SHALL BE PROTECTED WITH A MINIMUM OF 3-INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3 OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT.



Nobis Group® 18 Chenell Drive Concord, NH 03301 T(603) 224-4182 www.nobis-group.com



NOT ISSUED FOR CONSTRUCTION

# SITE MODIFICATIONS FOR SITE PLAN **COMPLIANCE** 119 OLD TURNPIKE ROAD

CONCORD, NEW HAMPSHIRE

APPLICANT/OWNER: **CORNERSTONE REALTY** HOLDINGS INC 72 MANCHESTER ST CONCORD, NH 03301-5129

NO.	DATE	DESCRIPTION	
REVISIONS			

SCALE: **AS NOTED** 

DATE:	APRIL 2025
NOBIS PROJECT NO.	100960.000
DRAWN BY:	KLR
CHECKED BY:	JIR
CAD DRAWING FILE:	

100960.000-C-005-NOTES & LEGEND.dwg

SHEET TITLE

GENERAL **NOTES AND** LEGEND

SHEET

