

August 04, 2017

Heather Shank, City Planner Planning Dept. City of Concord 41 Green Street Concord, NH 03301

Re: Concord Hospital – Emergency Department Exhaust Duct Architectural Design Review & Planning Board

Dear Heather:

Please find attached PDF documents describing the intent and design goals of the proposed Emergency Department Exhaust Duct. Our proposal is to shield the new ductwork with the same material as was used with the East Wing, 2007 Patient Tower.

Major highlights of the proposed project are:

- CMS (Centers for Medicare & Medicare Services) as well as NH Health & Human Services requires upgrades to the ED exhaust system to meet their various codes and standards.
- The proposed duct is 24" diameter, spiral stainless steel. The same regulations, ASHRE 170, require this duct go to the roof and extend ten feet above it.
- Our ED is not in compliance with current standards (2013 & 2010).
- We have investigated numerous interior pathways for this duct and it cannot be accommodated within the hospital without substantial hardship of the loss of square footage.
- We are adding no square footage to the building, only proposing an alteration to the exterior of the 1984 Patient Tower.
- Our Structural Engineer is requiring we remove the masonry veneer behind the duct in order to provide additional structural supports to both properly support the duct to the structural frame of the building (versus attachment to brick skin) as well as offset the weight of the duct work.
- We have prepared two overlays of a real photograph, one with the metal panel enclosure. The metal panel hides the removed brick and structure. The second photograph shows the ductwork with the galvanized structure and brick removed behind it. No panels involved. We prefer the metal panel option.

CONCORD HOSPITAL
IS A CHARITABLE
ORGANIZATION WHICH
EXISTS TO MEET THE
HEALTH NEEDS OF
INDIVIDUALS WITHIN
THE COMMUNITIES
IT SERVES.

- A plan view as well as an elevation has also been prepared. All materials will be presented on a 36" x 24" boards at the Architectural Design Review Committee Meeting on Tuesday the 8th.
- In addition, the Mechanical Engineer's drawings are also included.

We are eager to receive comments and planning board review of this exterior alteration such that construction can commence before winter snows.


Please call me if you need additional information to expedite your review/approval process. I can be reached at Concord Hospital at my office number of 603-227-7001.

Very truly yours,

Steven G David, RA NH Lic #1275 Staff Architect


Encl.

Cc; K. McCarthy, VP, Concord Hospital
D. Luce, Dir, Concord Hospital
S. Miller, RA, Concord Hospital
Chris Nadeau, PE, Nobis Engineering, Inc.
Richard Pizzi, CEO, Lavallee Brensinger Architects





ISSUANCE RECORD			
NO.	DATE	ITEMS	
1	07-12-2016	SCHEMATIC DESIGN	
2	11-09-2016	DESIGN DEVELOPMENT	



EMERGENCY DEPARTMENT EXHAUST ANALYSIS



Title: FIRST FLOOR PART PLAN – MECHANICAL

Date: NOVEMBER 08, 2016 Project No: YA15037ME

Confirm all existing conditions before proceeding OR before believing these conditions are true and up to date. Facility Plans are always a work in-progress!!.....

Revisions:

Drawn By: CSR

Approved By: WGF/WRG




CONCORD HOSPITAL

ER EXHAUST DUCT

SCALE:

07/21/2017






CONCORD HOSPITAL

EXPOSED DUCT

SCALE: 07/21/2017

LAVALLEE BRENSINGER ARCHITECTS




VEATON ASSOCIATES, INC.

66 Jackson Street
Littleton, NH 03561
603.444.6578
www.yeatonassociates.com
15037ME

ISSUANCE RECORD			
NO.	DATE	ITEMS	
1	07-12-2016	SCHEMATIC DESIGN	
2	11-09-2016	DESIGN DEVELOPMENT	

H:\Facilities\FACILITY PROJECTS\Projects\M-E-P- ALL\HVAC Upgrades\ED Waiting Exhaust\Dwgs\YA Drawings 11-08-16.pdf



EMERGENCY DEPARTMENT EXHAUST ANALYSIS



Title: FIRST FLOOR PART PLAN - MECHANICAL

Date: NOVEMBER 08, 2016
Project No: YA15037ME

Drawn By: CSR

Approved By: WGF/WRG

Revisions:

Confirm all existing conditions before proceeding OR before believing these conditions are true and up to date. Facility Plans are always a work in-progress!!.....

